



*Must extend full width of ingress and egress opening.

Notes

1. Tracking entrance shall be inspected daily. Deficient areas shall be repaired or replaced immediately. Any soil on the street shall be removed. This work shall be incidental to the contract.
2. Stone shall be removed and replaced when soil fills openings and/or directed by the engineer. This work shall be incidental to the contract.
3. Existing pavement shall be inspected and cleaned at least daily. This work shall be incidental to the contract.
4. Shall comply with WDNR Technical Standard #1057.
5. Tracking pad shall be installed prior to any traffic leaving the site.